

No.	Items of work	Unit	Rate	Quantity	Re- marks
11	T. W. windows with frames $3\frac{1}{2}'' \times 4\frac{1}{2}''$ with $\frac{1}{2}$ panalled and $\frac{1}{2}$ glazed shutters outside with iron bars, hooks, etc., complete.	S.ft.	Rs.	205	
12	Cement concrete perforated ventilators as per design.	"		214	
13	T. W. wrought and put up including wood oiling.	C.ft.		467.60	
14	Roofing with first class Mangalore tiles on teak reepers $2'' \times 1''$ etc., complete.	Sqr.		91.72	
15	Mangalore ridge tiles set in mortar	R.ft.		304	
16	Providing gutters with zinc sheet $3'$ with T.W. planks, etc., complete.	S.ft.		198	
17	T. W. Eaves board $9'' \times 1''$ plain	R.ft.		688	
18	Chunam plastering	Sqr.		173.50	
19	White and colour washing two coats	"		173.50	
20	Flooring with Mangalore square tiles on $3''$ concrete bed and cement pointing.	"		37.50	
21	Flooring with Kadappa slabs on $3''$ concrete bed and cement pointing.	"		15.86	
22	Masonry dwarf wall on slabs with plastering complete.	R.ft.		397	
23	Chocolate painting to doors, etc., two coats	Sqr.		5.51	
24	T. W. finial at ridge	Each		8	
25	Cement pointing to basement	Sqr.		12.00	
26	Coping over compound wall with brick in clay and chunam plastering and white washing, complete.	R.ft.		42	
27	Do do to gate pillars	Each		6	
28	Masonry borders to ventilators $6'' \times 1''$	R.ft.		400	
29	Providing T. W. gate with iron fittings, complete.	S.ft.		24	

N. G. KRISHNA IYENGAR,
Executive Engineer.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Abstract Notification dated 10th August 1931.

Attention of the public is invited to the detailed notification, dated the 31st July 1931, calling for tenders for constructing the Staff Quarters at Mysore, published in Part VI, pages 870 to 871 of the *Mysore Gazette*, dated 13th August 1931.

The latest date for receiving tenders is 2 P.M., on 29th August 1931.

Notification dated 11th August 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore, up to 2 P.M., on 7th September 1931, for constructing a block of Senior Operators' Quarters at Kolar Town.

1. The tenders will be opened in public at 2 P.M., on 7th September 1931. The work should be completed within three months and the monthly progress be not less than Rs. 1,000.

2. The plans, detailed estimates and the conditions may be seen at the Chief Electrical Engineer's Office, Bangalore, on all working days during the office working hours.

3. Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or in Government Promissory Notes, as earnest money and be superscribed "Tenders for Constructing a Block of Senior Operators' Quarters at Kolar Town," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which, his tender, will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the Notice Board in the Chief Electrical Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a week from the date of the notification of the acceptance.

10. Water for construction should be got at the contractor's own expense.

11. Specifications for works are those recognised by the Mysore Public Works Department and Marryot's specifications.

12. The contractor should be bound by the conditions of the Schedule of contract of the Electrical Department.

Serial No.	Items of work	Unit	Quantity	Rate
				Rs.
1.	Earthwork excavation and filling in basement ...	C.yd.	51	
2a	Stone jelly in chunam mortar concrete foundations ...	C.ft.	577	
b	Stone in clay foundation and basement ...	"	1,055	
c	Burnt brick in clay superstructure	"	2,551	
d	Stone slabs 5" thick roughly dressed and set in mortar	"	237	
e	Do 4" thick roughly dressed and set in mortar	"	24	
f	Chunam plastering two coats	Sqr.	56.36	
g	Chunam pointing	"	2.10	
h	Binding wall 1 1/8" x 9" brick in lime mortar and chunam plastering	R.ft.	44	
i	Plain cornice, 6" projection			
	Do		44	
j	Constructing sinks, complete...	Each	4	
k	Providing mortar and pestle....	"	2	
l	White and colour washing 2 coats	"	58.46	
3	Flooring with 3" lime concrete and chunam plastering with a floating coat of cement.	Sqr.	8.79	
4a	Roofing with first class Mangalore tiles on teak reepers 2" x 1" complete.	"	10.72	
b	Ridge tiles set in mortar and cement pointed	R.ft.	41	
c	Cuddapah slab terrace with Cuddapah slabs 1 1/2" thick, 3" concrete and 2 layers of flat tiles with plastering on top complete.	Sqr.	8.20	

Sl. No.	Items of work	Unit	Quantity	Rate
4d	Burnt brick in mortar 9" projection	R.ft.	63	Rs.
e	Burnt brick in mortar parapet wall 1½' high and 9" thickness as per plan.	"	59	
f	Ventilating tiles set in mortar	Each	8	
5a	Matti wood work wrought and put up with 2 coats of wood oiling.	C.ft.	34.17	
b	Doors with teakwood frames and honne wood battened shutters 1" thick and iron fixtures.	S.ft.	279.50	
c	Windows with teakwood frames and honne wood battened shutters 1" thick iron bars 5/8" diameter complete.	"	116.00	
d	Honnewood planks 1½" thick for shelves fixed on teakwood pegs complete.	"	48	
e	Chacolate painting 2 coats	Sqr.	13.28	
f	Expanded metal 3" x 1½" x 1/8" mesh fixed with teak wood frames complete.	S.ft.	116	
6a	Rolled steel girders fixed complete (Dorman Long & Co.) (Rate for Tata's make may also be quoted).	Cwt.	19.18	
b	Rain water down pipes 3" diameter fixed complete	R.ft.	20	
7	Brick in mortar pillar 1 1/8' x 1 1/8' x 7'-7" with base and capital and complete with including chunam plastering.	Each	1	
<i>Latrine.</i>				
1	Earthwork excavation and filling in basement	C.yd.	4	
2	Stone in clay foundation and basement	C.ft.	130	
b	Burnt brick in lime mortar superstructure	"	196	
c	Chunam plastering	Sqr.	4.91	
d	Chunam pointing	"	0.56	
e	White and colour washing two coats	"	5.47	
f	Cement plastering ½" thick	"	0.70	
g	Tar washing 2 coats	"	0.63	
3	Flooring with 3" concrete and cement plastering 1/2" thick.	"	0.38	
4	Fixing outlets, constructing drains, etc.	Item	1 Item	
5	Providing galvanized iron sheet tubs 12" x 6" x 6" with handles etc., complete with tarring.	Each	6	

C. M. CARIAPA,

Chief Electrical Engineer.